

# Production of accelerators and accelerator components in industry

Michael Pekeler

**RI Research Instruments GmbH** 

Friedrich-Ebert-Str. 1

51429 Bergisch Gladbach

#### **Foundation of RI Research Instruments**



- 1993: Foundation of ACCEL Instruments as management buyout of Siemens/Interatom. Start with about 30 key people, M. Peiniger and U. Klein as managing directors
- 2000: About 120 people working in the fields: RF cavities, Linacs and special products (AS department), superconducting magnets and circular accelerators (MA department) and optical beamlines (BL department)
- 2003: The MA department starts development of a superconducting proton cyclotron for medical application (200 MeV)
- 2004: about 270 people working for ACCEL
- 2007: Varian Medical Systems acquires ACCEL mainly because of the proton therapy technology (share deal)

2008: Varian divides ACCEL into the PT (proton therapy) branch and the RI (Research Instruments) branch

2009: Bruker Advanced Supercon, Inc acquires the RI branch of ACCEL as an asset deal from Varian. The MA and BL business is further transferred to the new BASC GmbH, a 100% daughter of Bruker, the AS business is transferred to the new RI Research Instruments GmbH a company owned 55% by Bruker and 45% by the management. The special manufacturing department (EB welding, UHV brazing, machining, chemical treatment stay at RI.



#### **RI Research Instruments GmbH**

Advanced Technology Equipment and Turn-Key System Supplier for Research, Industry and Medical worldwide



RF Cavities, Couplers, Auxiliaries Superconducting Accelerator Modules

**Electron and Ion Sources** 

**Linear Accelerators** 

Beam Diagnostic Elements and Particle Beamlines

Accelerator Equipment for Particle Therapy

**Specialized Manufacturing Projects** 



# **Manufacturing premises**



Electron beam welding UHV brazing Turning, milling Chemical treatment facilities Chemical polishing, electro- polishing





## **Superconducting cavities – series production**

#### TESLA (XFEL, ILC) cavities (>100)



CEBAF cavities (360)



#### SNS cavities (two types, low and medium beta, in total 109 cavities)







# **Superconducting cavities - prototypes**

#### Frankfurt CH mode cavity, 357 MHz



Chemical preparation, High pressure rinsing, assembly in our clean room Vertical test at University Frankfurt

# Nb/Cu coating technology



SRF Cavity production: Niobium on Copper technology for LEP, LHC





Chemical preparation, rinsing, assembly in clean room at our premises Vertical test at CERN

# **SOLEIL: Nb/Cu technology**

#### SOLEIL: 2.75 GeV, 500 mA light source

- Nb/Cu single-cell HOM damped cavities
- Designed and built by Saclay/CERN collaboration
- 352 MHz
- 1.5 MV/cavity
- LEP input couplers @ 200 kW
- loop HOM couplers







#### Two single cell cavities (352 MHz) in one vacuum vessel



#### **SOLEIL: 350 MHz storage ring twin module**



#### Module delivered to SOLEIL in May 2008.



# **500 MHz SRF modules**

NSRRC decided 1999 as the first Light Source to use SRF modules for TLS. CORNELL allowed a technology transfer to us of their technology.

Since then, the following contracts were awarded:

2000:2 SRF modulesfe2000:2 SRF modulesfe2000:2 SRF modulesfe2003:3 SRF modulesfe2005:3 SRF modulesfe

for NSRRC, for CORNELL, for CLS, for DLS, for SSRF,

Taiwan USA Canada Great Britain PR China

In total 12 RF modules have been produced and all modules are delivered, installed and accepted.

For comparison, to our knowledge:

Cornell built KEK built Mitsubishi built 5 SRF modules 9 SRF modules 2 SRF modules





#### **Turn key Cornell style SRF modules**

#### Scope can cover

- Cavity production
- Cavity surface preparation
- Cavity vertical test
- Coupler production
- Coupler conditioning
- HOM loads
- Module assembly
- Installation
- Commissioning
- Valve boxes
- transfer lines
- SRF Electronics
- Interlock and data acquisition system

Module performance: to be discussed with customer  $V_{acc} < 2 \text{ MV}, Q_0 = 5 \times 10^8$ 





### **Cavity preparation for vertical test**



**Closed loop BCP** 





HPR

Assembly in clean room

Packing and shipping for vertical test





#### **Cavity preparation and vertical test results**

**Preparation is done as follows:** 

- Degreasing
- Buffered chemical polishing (1:1:2), in closed loop chemistry, acid actively cooled to temperatures below 15 ° C
- Water Rising > 17 MWcm
- High pressure water rinsing (100 bar)
- Drying by pumping
- Assembly in class 100 clean room
- All test results achieved in consecutive preparations / tests
- All field values limited by available RF power



Summary 500 MHz Single Cell Cavity Tests



# Factory acceptance test with valve box and SRF electronics











#### **Transport/Logistics**





#### **Overseas transport**









#### **Installation into the NSRRC storage ring**



#### Module to be placed at its final position in the DLS storage ring





#### **Installation into the SSRF Storage Ring**









#### **Performance of DLS and SSRF modules**





#### **Valve boxes and transfer lines**



Valve box for 3 SRF modules

for 2 SRF modules

for a single SRF module



Siemens S7-300

Siemens S7-300

Open collector /

dry contact

Ethernet

#### **Data Acquisition and Operator Panels**





#### Main panel for cryogenic operation



#### **1.3 GHz twin cavity SRF modules**



#### **Preparation steps of 1.3 GHz 9-cell cavities**

Preparation steps	Done at
Manufacturing	ACCEL
100 µm BCP (closed loop)	ACCEL
Heat treatment 800 $^\circ$ C	DESY
20 µm BCP (closed loop)	ACCEL
High pressure rinsing (HPR)	ACCEL
Assembly in cleanroom	ACCEL
Transport under vacuum	ACCEL
Vertical test	DESY

All steps under our responsibility but using existing DESY furnace and test infrastructure





#### Vertical test results of 9-cell 1.3 GHz cvities

#### **TESLA cavities for BESSY and DESY\***



AC cavities prepared by DESY: BE cavities prepared by ACCEL: BCP, heat treated at 800 C and 1400 C BCP, only heat treated at 800 C



## SRF module production (1.3 GHz)

#### Twin TESLA Cavity Accelerator Module as Turn-Key System for FEL and ERL Application

Order for 4GLS in 04/2004

2 modules delivered in January and June 2006 Target Values cw:

Eacc > 15 MV/m @ Cavity Q > 1 E10

Prf > 8 kW per Coupler

TESLA Technology Transfer from e.g. DESY, JLAB, Cornell,

License Agreement on the Twin Cavity Module with FZ Rossendorf



#### Twin TESLA cavity module after assembly and just before delivery to Daresbury



# "Series" preparation of 1.3 GHz 9-cell cavities equipped with helium vessel



Contract from BESSY for 5 preparations (BCP, HPR) and clean room assembly with high power coupler for test in HOBICAT





#### **Turn-Key S-Band electron linear accelerators for synchrotron light sources**



#### **Delivered:**

SLS/PSI, CH	100	MeV		
DLS, UK	100	MeV		
ASP, Australia	100	MeV		
Final acceptance:				
PTB, Germany	0,5-50	MeV		
In Production:				
Taiwan Light Source 150 MeV				
Offered:				
Uni Nijmegen				
Technology Transfer from DESY (Dortmund Univ.)				

License Agreement on S-Band Lin. Collider Components with DESY



#### A 40 MeV cw proton / deuteron Linac for Israel





#### Set up for phase I beam characterization







#### **Source: Status and specification**

Parameter	Unit	Specification Value
Maximum beam current $H^+$ , $H_2^+$ , $D^+$	mA	5, 5, 5
Minimum beam current $H^+$ , $H_2^+$ , $D^+$	mA	0.04, 0.04, 0.04
Beam current spread (ripple) at maximum current	%	4
Beam current spread (ripple) at minimum current	%	6
Beam current stability	% @ 5mA	+/- 2.5
Beam current stability	% @ 0.04mA	+/- 5
Beam current adjustment accuracy for high current > 1mA	mA	0.1
Beam current adjustment accuracy for low current < 0.1mA	mA	0.005
Extraction energy	keV/nucleon	20
Extraction energy spread	eV/nucleon	+/- 30
Extraction energy stability	eV/nucleon	+/- 30
Extraction energy adjustment accuracy	eV/nucleon	100
Normalized rms emittance x/y	$\pi$ mm mrad	< 0.2/0.2

Particles Beam current	Protons	H2+	Deuterons
5.0 mA	N	M	
2.0 mA	Z	V	N
0.04 mA	N	N	V

#### Since November 2007 accepted

 Table 2-1 EIS specification (to be measured at the LEBT diagnostics)



#### **RFQ: RF installation finalised**





#### **RFQ conditioning status**



#### **Prototype supercondcuting module**





#### **General Design**

- Houses 6 HWR and 3
   superconducting solenoids for focusing
- Acceleration of protons and deuterons from 1.5 MeV/u on
- Very compact design in longitudinal direction
- Cavity vacuum and insulation vacuum separated





#### **Chemical treatment of HWR: closed loop BCP 1:1:2**

All cavities received a new preparation after vertical test and helium vessel welding Closed loop BCP also possible with helium vessel welded.





#### **Preparation of series cavity for vertical test**

Preparation of a cavity without helium vessel welded



# Test of cavity with helium vessel welded and instrume tuner mounted



instruments

#### **Summary of cavity test results**



Epeak [MV/m]



LB-2, LB-7, LB-3, and LB-4 tested before helium vessel welding

research

instruments

- LB-6 and LB-5 tested after helium vessel welding
- In all test of series cavities, multipacting was much reduced compared to the prototype cavity
- Field emission only seen at very high field levels



#### **Cavity tests after installation into the linac**





#### Why Proton Therapy for cancer treatment



Protonen vs. Photonen in der Krebstherapie



#### **Superconducting Proton Cyclotron**







#### **Proton Therapy Systems**



#### Superconducting 250 MeV Cyclotron for Paul Scherrer Institute (PSI) and RPTC, Munich







#### **Superconducting Proton Cyclotron installed**





#### **Components and Subsystems of a 250 MeV Cyclotron for Varian Medical Systems**





#### **Components and Subsystems of a 250 MeV Cyclotron for Varian Medical Systems**



150 kW rf Power Amplifier. Based on innovative semiconductor technology

